



PTY LTD

TM

Trustee for: The Greensafe Trust

BSA Lic No. 075266

ACN 010 973 609

ABN 38 382 331 854

16th of January 2022

Nick Allen
Shire of Whyndam East Kimberley
20 Coolibah Drive,
PO BOX 614
KUNUNURRA W.A. 6743

Dear Nick,

This is our quotation for the supply and installation of a GREENSAFE RETRACTABLE CANOPY at Kununurra.

GREENSAFE Pty Ltd have successfully installed over 80 installations around Australia over the last 26 years. Our company is the only company in Australia who installs motorised retractable shade covers over bowling greens and swimming pools. Our canopies are renowned Australia wide for our quality workmanship and ongoing support.

GREENSAFE Pty Ltd have installed canopies at Broome Recreation and Aquatic Centre, Karratha Leisure Centre, Jabiru pool and other swimming centres. All GREENSAFE structures are guaranteed for 10 years, and all moving parts are warranted fully (not pro rata) for 5 years.

The canopy is made from 90% shade factor, commercial grade, all monofilament knitted shade cloth sewn with Tenara thread which is guaranteed for 15 years against UV degradation. The cloth is supported on six main cables, strained between pairs of steel posts, and drawn backwards and forwards by stainless steel wires driven by six, one and a half hp motors at one end of the pool.

The main posts would be 3.7M (12 feet) high at the walkway level and the tightness of our cables means that the cover is approximately 3.3M (11 feet) above the pool at its lowest point. The canopy would take approximately 2 minutes and 20 seconds to extend or retract and does not need to be taken down in the event of a cyclone or cyclone warning. The temperature of the pool will be cooled by up to 15 degrees.

Construction time is approximately two to four weeks, during which time the pool would be unavailable for swimming. All construction is to engineer design and certification. Access is required to the site for machinery etc., but this would be coordinated with a member of your staff to ensure as little disruption as possible to the public.

Cost for the above supplied and installed.....\$273,380.00 plus 10% GST.

The only extra to the above price would be your Council approvals, inspections, and supply of power to the first post. As these costs are unknown, I cannot include them in the price.

This is a FIXED PRICE QUOTATION and there will be no rise or fall except in the case of rock where the extra cost would be charged at verified cost only. This quotation is subject to not having to go into quarantine.

Kind regards,

Michelle Taylor
Director
0488 005 219