

12<sup>th</sup> February 2018

Quote valid for 30 days

**Quote - Concrete basketball ½ court, 15m x 14m  
 At Guda Guda Community, Great Northern Highway, Wyndham  
 For Community Housing Ltd**

**Quote Includes -**

- Earthworks (level earth pad)
- Formwork & installation of formwork
- Preparation of reinforcement
- Place & finish of Concrete
- Plant hire
- Materials & their delivery

<b>Line painting for Court</b>		\$ 1 705.00
<b>Labour/Plant Hire/Travel -</b>	Labour - earthworks (level pad 272m2 + crusher dust border after pour)	\$ 1 600.00
	Plant hire - Bobcat/excavator/dingo	\$ 1 150.00
	Travel – earthworks 3 vehicles x 180km @ \$1.60/km	\$ 864.00
	Labour - concrete form, prep, place & finish – 210m2 @ \$38/m2	\$ 7 980.00
	Travel – concrete works 2 vehicles x 360km @ \$1.60/km	\$ 1 152.00
	Sam cuts – 87m @ \$8/m	<u>\$ 696.00</u>
	Sub-total	\$ 13 442.00
	GST	<u>\$ 1 344.20</u>
	TOTAL	\$ 14 786.20

<b>Materials -</b>	N25 Concrete	23.5m3	\$ 14 100.00
	SL72 mesh	18 sheets	\$ 1 620.00
	Plastic	2 rolls	\$ 370.00
	50/65 chairs	4 bags	\$ 160.00
	Wire	1 roll	\$ 20.00
	Tape	2 rolls	\$ 20.00
	Delivery – reinforcement		\$ 200.00
	Crusher Dust	7m3	\$ 1 170.00
	Pindan sand	30m3	<u>\$ 3 630.00</u>
	Sub-total		\$ 22 995.00
	GST		<u>\$ 2 299.50</u>
	TOTAL		\$ 25 294.50

*Guymer*  
**Concreting and Construction**

ACN 619715570  
ABN 36619715570  
QBSA Licence 1152350  
PO Box 638, Kununurra WA 6743

Lee 0428137753  
Kate 0438310799  
[guymerconcreting@hotmail.com](mailto:guymerconcreting@hotmail.com)

Labour/Plant Hire (inc.)	\$ 14 786.20
Materials (inc.)	<u>\$ 25 294.50</u>

**TOTAL (inc.) \$ 40 080.70**

We appreciate the opportunity to provide you with a quote for this project.

Quote is calculated on 210m<sup>2</sup>, 100mm thick slab with reinforcement.

Earth pad made from pindan sand is calculated on being 17m x 16m x 0.1m in size and levelled as per concrete levels. To be done first.

Crusher dust allows for 1m x 0.1m strip around the perimeter of concrete. To be done last.

Saw cuts are to control cracking, they are optional. They would be done the day following the pour.

Job would take 4 or 5 days to complete.

If you have any questions, please don't hesitate to call.

**Lee Guymer**  
**0428 137 753**

PO Box 638 Kununurra, WA 6743  
[guymerconcreting@hotmail.com](mailto:guymerconcreting@hotmail.com)  
Lee 0428137753 Kate 0438310799