

Ablecon Pty Ltd as trustee for Jesan Trust

trading as

# KIMBERLEY WATER CARTING

ABN: 21 954 912 473

## Quotation

PO Box 822  
Kununurra, WA 6743

kimberleywater@westnet.com.au

Jeff Walters 0417 682 585

**Kununurra Campdraft & Rodeo**  
**PO Box 891**  
**Kununurra WA 6743**

Date	Quotation #
19/07/2020	Q180912

Description	Total exc GST
<p>Location: Kununurra Rodeo Ground</p> <p>SCOPE OF WORKS:</p> <p>Establish a safe work area. Exclude general public. Locate any power, water or other utilities. Minimise hazards - dust, exposure to heat / sun, dehydration, person / vehicle interaction.</p> <p>Civil Works: Campdraft Arena &amp; Cut Out Yard</p> <p>Box out existing materials (spoils). Cut floor to level - 150mm deep (+10mm, -30mm). Backfill with sand as selected by the Kununurra Campdraft / Rodeo Committee. Sand to be screed off even and consistant throughout.</p> <p>Civil Works: Viewing Mound</p> <p>Spoils to be utilised to construct a spectator viewing mound on the up wind / eastern side of the Campdraft Arena, near ammenities and canteen. Mound to have a flat top. Slope to arena not to be more than 1 in 5 gradiant</p> <p>Works Completion:</p> <p>All ground to be smooth. Haulroad to be reinstated / graded and no rutts. All disuse or unsuitable materials and rubbish to be disposed of at Kununurra landfill.</p> <p>Maintenance Tooling:</p> <p>A sand drag to be designed, constructed and delivered to Kununurra Campdraft Complex to enable the club to maintain an even and flat surface during and after events. Drag to be constructed from new materials and painted (colour to be chosen by the committee). Towing to suit small tractor or similar.</p> <p>Our quotation price ( excluding GST)</p> <p>Additional: Sand to be supplied &amp; guaranteed for 5 years by Kununurra Gravel</p>	
<b>Total exc GST</b>	\$98,800.00
<b>GST</b>	\$9,880.00
<b>Total inc GST</b>	<b>\$108,680.00</b>